

18 Feb 2009

Mr. Marshall Riddle  
131 Mt. Sterling Dr.  
Lynchburg, Va. 24502

Re: TM# 150-3-1E1 (7.9 Acres +/-)  
US 460E  
Bedford County, Va.

Dear Mr. Riddle,

Per your request on 17 February 2009, I conducted a feasibility evaluation on the referenced parcel. I evaluated the site to determine its suitability for a conventional drain field to serve a proposed, three or four bedroom residence. The portion of the site evaluated consisted of the front left portion of the lot, along US 460. The site was evaluated utilizing hand auger borings.

Hand auger borings conducted on site indicated that the lot should support a standard (pipe and gravel trenches) drain field system sufficient to support a four bedroom home (or 600 gallons per day of flow). Suitable drain field soils were identified as deep as 60-72" along the front of the lot. *Final system design will rely heavily on final home location and dimensions.*

In closing, it should be noted that this feasibility evaluation DOES NOT constitute a permit. Per your request, no formal permit or certification paperwork was completed at this time. The recommendations of this feasibility letter are meant to present you with some of the design options which could serve the site. Obviously, I do not mean to account for every possible home site or effluent treatment and dispersal option in the scope of this letter.

Again, as with any proposed home, final drain field system design is highly contingent on final home location, driveway routing and many other site design and grading factors.

Please contact me should you require any further clarification of this feasibility report or any of the recommendations contained in it.

Sincerely,  
**Hurt & Proffitt, Inc.**

Randal L. Doss, AOSE # 274